

Typical DataStorm Installation

A typical DataStorm of Florida installation is done to MotoSat's specifications. Always keeping in mind our high standards and care to detail. We care for your equipment and vehicle as if it were ours.

A Typical Installation may include the following:

Major Parts:

1. DataStorm or Television Antenna
2. Controller
3. Modem
4. Router, (router purchase extra)
5. BOW for TV with DataStorm if necessary, (BOW purchase extra)
6. Television Antenna

Mounting exterior equipment:

1. Cleaning and preparing the roof surface area prior to installation
2. Carefully lifting the equipment to the roof surface
3. Attaching the antenna directly to the roof surface
4. Attaching the wires, wrapped in loom directly to the roof surface
 - A. DataStorm systems includes 3 cables; 1 control & 2 coax
 - B. DataStorm systems with BOW includes up to 2 coax cables
 - C. Televisions system normally includes 2 coax cables
5. Drill 1 one inch hole through the roof surface into an interior cabinet area (not in slide)
6. Sealing all screws holes and the wire hole, to be made water tight with the industry standard and MotoSat's prescribed Dicor sealer

Mounting interior equipment:

1. Install Controller, Modem and Router
2. Attach all wires securely, per industry standards

Clean up, system operating instructions and final paperwork are all that is left. DataStorm of Florida will give you detailed instructions and complete information through the sale, installation and future use of your MotoSat Internet and/or Television Antenna. Our service doesn't end with the delivery of your antenna. We will be your 1st Tier Technical Support if that time ever arises.

090815